

CAPE MAY COUNTY MUNICIPAL UTILITIES AUTHORITY  
1523 Route 9 North  
Cape May Court House, NJ 08210  
Phone: (609) 465-9026 Fax: (609) 465-9025

ADDENDUM NO. 3  
to the  
CONTRACT DOCUMENTS

SECURE SANITARY LANDFILL  
LEACHATE PUMP STATIONS  
CONTROL/POWER REPLACEMENT

CONTRACT SLF-03-23

---

To All Document Holders:

The following changes, additions and/or deletions are hereby made a part of the Contract Documents for the above referenced contract as fully and completely as if the same were fully set forth herein:

**SPECIFICATIONS**

1. In Section 010100 – Summary Of work, paragraph 1.3.A, add the following subparagraph”

“8. The Authority will provide all PLC programming, PLC functional testing (including scale setup for instrumentation) and new fiber optic network setup and startup. The Contractor shall be responsible for functional testing of all hardware as specified herein. Refer to Sections 250300 and 260510 in regards to, respectively, instrumentation calibration and testing requirements.”

2. In Section 010100 – Summary of Work, paragraph 1.4.F.1, in the first line, change the word “generators” to “controls”.
3. In Section 012000 – Price and Payment Procedure, paragraph 1.5.D.1, in the first line, after the word “include”, insert the following:

“all work described on drawing number E-121, Key Note 12, as well as”

**DRAWINGS**

1. Drawing No. E-120:

1.1. For poles SLF-W-11 and SLF-W-13, change the Key Note reference from 13 to 13A.

1.2. Add Key Note 13A as follows:

“13A. For poles SLF-W-11 and SLF-W-13, reinstall bracket for existing light fixture on new pole. The Authority shall install a new fixture on the relocated bracket.”

2. Drawing No. E-121:

2.1. For pole SLF-W-1, add a Key Note reference to Note 7A.

2.2. For pole SLF-W-2, change the Key Note reference from 7 to 7B.

2.3. Add Key Note 7A as follows:

"7A. The existing lighting control panel on existing pole SLF-W-1 shall be relocated to the new pole SLF-W-1 to provide power for lights on poles SLF-W-1, SLF-W-2, SLF-W-3, SLF-W-5, SLF-W-11, SLF-W-12 and SLF-W-13."

2.4. Add Key Note 7B as follows:

"7B. Reinstall bracket for existing light fixture on new pole. The Authority shall install a new fixture on the relocated bracket."

3. Drawing No. E-122:

3.1. For pole SLF-M-4, add a Key Note reference to Note 8A.

3.2. For poles SLF-M-2 and SLF-M-3, change the Key Note reference from 8 to 8B.

3.3. Add Key Note 8A as follows:

"8A. The existing lighting control panel on pole SLF-M-4 shall be relocated to the new SLF-M-4 pole to provide power for lights on poles W42991, SLF-M-1, SLF-M-2, SLF-M-3, and SLF-M-4."

3.4. Add Key Note 8B as follows:

"8B. Reinstall bracket for existing light fixture on new pole. Authority will install new fixture on relocated bracket."

3.5. Add to the end of Key Note 5 as follows:

"Terminations within the building shall include fiber optic patch panel terminations at the network's head end cabinet."

3.6. Add the following to the end of Key Note 16 as follows:

"The Kupper box is the interface between the SLF on-site generation facility and PJM. Existing power and communications wiring within the two conduits shown on detail 4/E-122 may need to be extended to the new pole to match existing."

3.7. Add General Note 6 as follows:

"The Authority owns all overhead power lines, fiber lines noted to be removed, and poles noted to be removed after pole #W42986 (point of ACE interconnection). Additional utility owned cables are present from pole #W42986 to pole #SLF-M-3 (Scalehouse #2) shown on drawing E-122 including Verizon fiber, GSL fiber, copper telephone cable, ACE fiber to the Kupper box on pole #W42988, and ACE fiber from the Kupper box to the SLF

generation facility. The Contractor shall be responsible to extend and/or splice these cables as necessary for relocation to new poles in accordance with applicable utility requirements. Refer also to specification sections 010100, 260100, and 260501 for additional utility coordination requirements. Any fees to the respective utility companies required for coordination with or relocation of the utilities will be paid by the Authority as a direct pass-through expense, with no markup from the Contractor.”

**All bidders shall acknowledge the receipt and acceptance of this Addendum No. 3 by indicating Addendum Number in the space provided on the Acknowledgement of Receipt of Addenda Form. Bids submitted without this Addendum Acknowledgement will be considered non-responsive.**