

CAPE MAY COUNTY MUNICIPAL UTILITIES AUTHORITY  
1523 Route 9 North  
Cape May Court House, NJ 08210  
Phone: (609) 465-9026 Fax: (609) 465-9025

ADDENDUM NO. 1  
to the  
CONTRACT DOCUMENTS

OCEAN CITY REGION  
32<sup>ND</sup> STREET PUMP STATION  
PIPING AND PUMP UPGRADES

CONTRACT OC-18-22

---

To All Document Holders:

The following changes, additions and/or deletions are hereby made a part of the Contract Documents for the above referenced contract as fully and completely as if the same were fully set forth herein:

**DRAWINGS**

1. On Drawing Nos. 3 and 4, delete note 13 and replace it with the following:

“13. ALL ELECTRICAL WORK SHALL BE PERFORMED BY THE OWNER:

- THE OWNER'S WORK TO BE PERFORMED PRIOR TO THE CONTRACTOR PERFORMING ANY PHYSICAL WORK AT THE SITE SHALL INCLUDE VFD INSTALLATION, CONDUITS, HANGERS, SUPPORTS AND CONTROLS.
- THE OWNER'S WORK TO BE PERFORMED WHILE THE CONTRACTOR IS PERFORMING PHYSICAL WORK AT THE SITE SHALL INCLUDE DISCONNECTION OF EXISTING AND RECONNECTION OF NEW CONDUCTOR CONNECTIONS FROM THE PUMP MOTORS TO THE VFD CABINET AND FROM THE METERS TO THE CONTROL PANEL AND APPURTENANCES.
- THE CONTRACTOR SHALL NEATLY PLACE ALL CONDUCTORS FROM THE PUMP MOTORS AND METERS IN A LOCATION ACCESSIBLE TO THE OWNER, AND SAFE FROM DAMAGE.
- THE CONTRACTOR SHALL NOTIFY THE OWNER 48 HOURS IN ADVANCE WHEN EACH UNIT IS READY FOR DISCONNECTION AND RECONNECTION. “

2. Drawing No. 7 – ELEVATION LOOKING EAST:

Change the note below the lower Section A/7 arrow from:

“EXISTING PIPING TO REMAIN (TYP)”

to

“NEW PIPING (TYP)”

## **SPECIFICATIONS**

### 1. Section 010100 – Summary of Work

- Add to paragraph 1.03.C the following:
  1. The Owner's work to be performed prior to the Contractor performing any physical work at the site shall include VFD installation, conduits, hangers, supports and controls.
  2. The Owner's work to be performed while the Contractor is performing physical work at the site shall include disconnection of existing and reconnection of new conductor connections from the pump motors to the VFD cabinet and from the meters to the control panel and appurtenances.
  3. The Contractor shall neatly place all conductors from the pump motors and meters in a location accessible to the Owner, and safe from damage.
  4. The Contractor shall notify the Owner 48 hours in advance when each unit is ready for disconnection and reconnection.

### 2. Section 015400 Bypass Pumping System

- Section 015400, paragraph 1.02 C: Delete "The Contractor shall include one standby pump. The standby pump unit shall be piped into the inflow and to the bypass piping so that, upon starting the engine or motor, the standby pump will pick up the flow. "

and replace with

"The Contractor shall include two standby pumps. One for each of the two primary pumps shown on Drawing No. 10 of the plans. The standby pump units shall be piped into the inflow and to the bypass piping so that, upon starting the engines or motors, the standby pumps will pick up the flow. "

**All bidders shall acknowledge the receipt and acceptance of this Addendum No. 1 by indicating Addendum Number in the space provided on the Acknowledgement of Receipt of Addenda Form. Bids submitted without this Addendum Acknowledgement will be considered non-responsive.**